BRUHAT BANGALORE MAHANGARA PALIKE

Office of the Executive Engineer, (SWD, Bommmanahalli Zone), 9th Floor, Shopping Complex, 4th Block, Jayanagar, Bangaluru-560 011

No. EE/SWD-BOM/Adde-2/ 02 /2024-25 Dated: 02-04-2025

ADDEDUM-02

SHORT TERM TENDER NOTIFICATION

(Through **KPP Portal** only)

Name of work : Construction of Flood Protection Structures to Storm Water Drain including RCC Retaining walls, Water retention Structures, Nature Based Solutions Structures, Culverts and Bridges Under Karnataka Water Security and Resilience Program (KWSRP) With Externally Funded Project (World Bank) in BommanahalliZonePackage-01 (31 Works). Tender amount Rs.16350.39 Lakhs

Reference: 1.This office Tender Notification: EE/SWD-BOM/TEND/02/2024-25
Dated: 10-03-2025

2.Tender Indent Number :BBMP/2024-25/FP/WORK_INDENT6829

****

With respect to above subject, following Addendum to the above tender work is issued to be read has below:

SL No.	Section of tender	Cluase/ Item No	As published in KPPP BOQ	As Amended & to be read as
1	BOQ	Item10	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Open Foundation) with in all lifts and lead as directed by engineer-incharge-of work	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **Including cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Open Foundation) with in all lifts and lead as directed by engineer-incharge-of work
2	BOQ	Item11	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve

			durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Sub Structure)	durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **including cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M25 Grade (Sub Structure)
3	BOQ	Item12	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Open Foundation) with in all lifts and lead as directed by engineer-incharge-of work	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **including cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Open Foundation) with in all lifts and lead as directed by engineer-incharge-of work
4	BOQ	Item13	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Sub Structure) with in all lifts and lead as directed by engineer-incharge-of work	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **including cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Sub Structure) with in all lifts and lead as directed by engineer-incharge-of work
5	BOQ	Item14	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, Ordinary	Ready Mix Concrete (RMC) with Cement & Cementitious Materials Providing and laying in position Ready Mixed or Batch Mixed concrete as per IS 10262 mix design procedure for Cement Concrete works in all types of Structures other than Road works, using coarse aggregate and fine aggregate derived from natural sources, **Ordinary**

			Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **but excluding the cost of centering, shuttering, finishing and reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Solid Slab Super Structure) with in all lifts and lead as directed by engineer-incharge-of work	Portland Cement (OPC) @ 75% & GGBS @ 25% proportion, admixtures to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; **including cost of centering, shuttering, finishing and excluding the cost of reinforcement** as per direction of the Engineer-in-charge RMC M30 Grade (Solid Slab Super Structure) with in all lifts and lead as directed by engineer-incharge-of work

All other terms and conditions remain unchanged.

Srilanka 22/4/25

Executive Engineer,
SWD, Bommanahalli Zone
Bruhat Bengaluru Mahanagara Palike

Copy submitted to :

1. Copy submitted to Engineer- in- Chief designated Chief Engineer, SWD, BBMP for kind information.
2. Superintending Engineer (SWD) for kind information.
3. Office Copy.